

PROJECT: PROPOSED RENOVATION OF OSHC AUDITORIUM
 OWNER: OSHC
 LOCATION: NORTH AVE., COR. AGHAM ROAD, DILIMAN, QUEZON CITY

Item	Description	Quantity	Unit	Statement of Compliance
A	PRELIMINARIES			
1.00	Renovation Permit		lot	
2.00	Safety Requirements, PPE		lot	
3.00	Scaffoldings Rental		sq.m	
4.00	Water Consumption		mo	
5.00	Electricity		mo	
6.00	Barracks and Warehousing		mo	
7.00	As-Built Plans		lot	
8.00	Mob/ Demob		lot	
Sub Total :	PRELIMINARIES			
B	ELECTRICAL WORKS (if applicable)			
Sub Total :	ELECTRICAL WORKS			
C	MECHANICAL WORKS			
1.00	Restoration of Window Blinds Opener		l.s	
	Repair of Handles of Blinds Rotary Opener			
2.00	Restoration of Stage Mechanical Curtain		l.s	
	Repair / Restoration of Mechanized Curtain Opener			
Sub Total :	MECHANICAL WORKS			
D	PAINTING WORKS			
1.00	EXTERIOR WALL			
1.1.0	Water Tank		sq.m	
1.2.0	Canteen		sq.m	
1.3.0	Auditorium		sq.m	
2.00	INTERIOR WALL			
2.1.0	Audio Visual Room or Projection Room		sq.m	
2.2.0	Canteen		sq.m	
2.3.0	Auditorium		sq.m	
3.00	PANEL DOORS			
3.1.0	Auditorium		sq.m	
3.2.0	PWD Toilet		sq.m	
3.3.0	Audio Visual Room or Projection Room		sq.m	
4.00	CEILING			
4.1.0	Auditorium		sq.m	
4.2.0	Canteen		sq.m	
5.00	FLOOR			
5.1.0	Wood Parquet Flooring		sq.m	
6.00	PRE-PAINTED GUTTER (if applicable)			
6.1.0	Auditorium		ln.m	
6.2.0	Canteen		ln.m	
7.00	DOWNSPOUT			
7.1.0	Auditorium		ln.m	
7.2.0	Canteen		ln.m	
Sub Total :	PAINTING WORKS			
E	MISCELLANEOUS WORKS			
1.00	Repair / Restoration of Defective / Damaged Door Accessories		l.s	
	Scope: Repair of Handles of Blinds Rotary such as Handles, Lockset and Hinges including upholstery			
1.1.0	Auditorium			
1.2.0	PWD Toilet			
1.3.0	Audio Visual Room or Projection Room			
2.00	Restoration of Wood Parquet Flooring		sq.m	
3.00	Audio Visual Room or Projection Room			
3.1.0	100 x 600mm x 2mm thk Scratch Free Vinyl Tile from Stair to Floor		sq.m	
4.00	Ramp for Person with Disability (see detailed comp.)		l.s	
	Scope: Construction on new Ramp for Person with Disability			
	Modification of Stage Platform to accommodate the new Ramp (refer to plan)			
5.00	Replacement of Gutter: 0.40mm thk 14" Pre-painted. Need to remove Spanish Roof Tile for properly remove the Existing Gutter			
5.1.0	Auditorium.		ln.m	
5.2.0	Canteen		ln.m	

PROJECT: PROPOSED RENOVATION OF OSHC AUDITORIUM
 OWNER: OSHC
 LOCATION: NORTH AVE., COR. AGHAM ROAD, DILIMAN, QUEZON CITY

Item	Description	Quantity	Unit	Statement of Compliance
6.00	Replacement of Downspout (4" diameter PVC Pipe, Neltex,S-1000,4" diameter 90 Deg. PVC Elbow, Neltex,PVC Clips / Holders (Fabricated 4mm Flatbar))			
6.1.0	Auditorium		ln.m	
6.2.0	Canteen		ln.m	
7.00	Replacement of Hard Wood Louver Door at Stage		sq.m	
8.00	Replacement of Ceiling at Hallway going to PWD Toilet		sq.m	
10.00	Disable Ramp with Roof (near flagpole)			
10.1.0	Disable Ramp		sq.m	
10.2.0	Steel Handrails		ln.m	
10.3.0	Roof		sq.m	
11.00	Project Billboard			
11.1.0	a. OSHC Project Billboard		nrs	
11.2.0	b. COA Billboard		nrs	
Sub Total :	MISCELLANEOUS WORKS			
Total				